

Water/Structural Testing

Porch Windows Direct
Attn: Brandon Williamson
8100 Old Cedar Ave S. #350
Minneapolis, MN 55425

Date: April 8, 2025
Author: Richard Luna
Report Number: ESP043898P.2

Water/Structural Testing of Xtend Porch Window 36 x 72"

It is our policy to retain components and sample remnants for a minimum of 30 days from the report date, after which time they may be discarded. The data herein represents only the item(s) tested. This report shall not be reproduced, except in full, without prior permission of Element Materials Technology. Unless otherwise specified, measurement uncertainty was not taken into account when making statements of conformity to a specification.

EAR Controlled Data: This document contains technical data whose export and re-export/retransfer is subject to control by the U.S. Department of Commerce under the Export Administration Act and the Export Administration Regulations. The Department of Commerce's prior written approval may be required for the export or re-export/retransfer of such technical data to any foreign person, foreign entity or foreign organization whether in the United States or abroad.

This project shall be governed exclusively by the General Terms and Conditions of Sale and Performance of Testing Services by Element Materials Technology. In no event shall Element Materials Technology be liable for any consequential, special or indirect loss or any damages above the cost of the work.

EAR-CONTROLLED DATA**INTRODUCTION:**

This report presents the results of Screen testing per ASTM E547-00 (2016), ASTM E330-E330 M-14 (2021)
Samples were received and tested at Element Des Moines on March 14th, 2025.

SAMPLE DESCRIPTION:

Product Name	:	Xtend Porch Window
Product Type	:	Vinyl Glazed 3 Season Porch Windows
Series/Model #	:	4 Track/4 Sashes
Overall Frame Size	:	36" X 72"
Screen	:	Full
Frame Construction	:	Powder Coated Aluminum
Sash Construction	:	Powder Coated Aluminum
Glazing System	:	10 Gauge Clear Marine Grade Double Polished Vinyl
Screen Construction	:	<i>Phiffer BeterVue</i>
General Installation Description-Clip-Screw-Fin	:	Integral Flange
Installation Method	:	Install Screws fastened through nailing fin of extrusion into wooden enclosure.



EAR-CONTROLLED DATA

TEST RESULTS:

Water Penetration Limited Water

SAMPLE	Pressure	Reported	Results
36 x 72	0	0	No Water Leakage

Structural Pressure was held for 10 seconds

SAMPLE	Pressure	Reported	MPH
36 x 72	60 psf	60 psf	153

CALIBRATED TEST EQUIPMENT:

- PT-162-018 - Spray Rack
- PT-162-050 - ATS System

Due Date - 06/18/2025

Due Date - 06/18/2025

DISPOSITION OF SAMPLES:

The sample will be disposed of as trash unless otherwise requested by client.

Respectfully submitted,

Richard B. Luna
Fenestration Manager
Fenestration Department